

Subtask 3.2. Comparative assessment of alternative methods used for decommissioning reactor compartments

Alternative methods of concepts C and D (disposal as a whole) currently used for deferred decision in the international practices of the long-term storage.


Negative aspects: safety, limited selection for disposal options, non-compliance to international recommendations of the IAEA in relation to the radioactive waste disposal and may will be in conflict with the IAEA requirements which are assumed to be used in the future, especially if to take into account that the decommissioning is expected after 50 years of safe storage.

> Preliminary indicative assessment of decommissioning methods

| Concept | man-hours | years | Collective dose (man – mSv) | Cost, (million Eur) |
|-----------|-----------|-------|--------------------------------------|---------------------------|
| Concept C | 117 000 | 3.5 | 110 | 7.8 |
| Concept D | 214 000 | 5.5 | 190 | 12.0 |
| Concept A | 328 000 | 6.6 | 600 - 700 | 24.0 |
| Concept B | 369 000 | 7.0 | 700 - 800 | 25.0 |

Concept A (large-size fragmentation) - minimization of the dose loads if compare to Concept B (small-size fragmentation). Concepts A and B require demolition equipment, concrete crushing, special container for the reactor vessels transportation/disposal as a whole. Concept A and B require specialized installations and equipment for mapping of RW inside reactor compartment. Comparing to the concept A, concept B requires more precise cutting of the concrete and decontamination; and, in its turn, it provides for better radwaste management (usage of standard containers), safety, allows to minimize quantities of the radwaste for disposal.

5



E AND

Subtask 3.2. Comparative assessment of alternative methods used for decommissioning reactor compartments

Option A is characterized by:

- moderate labour costs and collective radiation exposure;
- fewer amount of equipment required for decommissioning works compared to option B;
- fewer amount of secondary RW compared to option B;

Option B is inferior to option A by the following indicators:

- Iabour costs
- collective radiation exposure;
- amount of equipment and systems for waste decontamination,
- costs of waste processing and purification of the gas environment;
- amount of the secondary waste to be generated.


However, implementation of option B is characterized by:

- reduction of primary RW; (RC and the nuclear installation equipment is to be cut into small fragments, which are subject to decontamination with the aim of exempting most of the metal waste from regulatory control, and, thus, it is possible to minimize the RW amount to be disposed of);
- reduction of volume and number of RW packages to be disposed of;
- reduction of the number of standard size protection containers to be developed.
- reduction in the size of RW repository facilities, which will result in cost saving during RW repository construction


7




PRELIMINARY STUDIES FOR THE DECOMMISSIONING OF THE REACTOR COMPARTMENTS OF THE FORMER PALDISKI MILITARY NUCLEAR SITE AND FOR THE ESTABLISHMENT OF A RADIOACTIVE WASTE REPOSITORY



| indicative expert estimation | | | | | | |
|--|--------|------------|--------|--|--|--|
| Evaluation criteria | Option | Evaluation | Points | | | |
| Time of work | Α | 100 | score | | | |
| | В | 95 | score | | | |
| Man-hours for the whole set of works | Α | 100 | score | | | |
| | в | 90 | score | | | |
| Dose loads for the whole set of works (man – mSv) | Α | 100 | score | | | |
| | В | 85 | score | | | |
| Amount of primary RW to be generated (cubic m.) | Α | 60 | score | | | |
| | В | 100 | score | | | |
| Amount of the secondary RW to be generated (% from Σ RW) | Α | 100 | score | | | |
| | В | 70 | score | | | |
| Quantity of standard sizes of the containers to be newly developed | Α | 75 | score | | | |
| (transport and disposal containers, pcs.) | В | 100 | score | | | |
| Economics (cost estimation, mln. Euro) | Α | 100 | score | | | |
| | В | 90 | score | | | |
| Safety assessment (general safety) | Α | 75 | score | | | |
| | В | 95 | score | | | |
| Environmental impact assessment | Α | 85 | score | | | |
| | B | 80 | score | | | |



| Subtask 3.3. Development of the concept of decommissioning selected as a result of the assessment INDICATIVE WORK SCHEDULE AND SEQUENCE OF WORKS | |
|--|-------|
| 1. Preparatory works | |
| 1.1 Preliminary studies on decommissioning in 2014- 2015 | |
| 1.2 Introduction of changes into legal and regulatory framework of the Republic of Estonia (RE) | |
| 1.3 Comprehensive engineering and radiological survey of the Site and reactor compartments (RCs) | |
| 1.4 Feasibility study and environmental impact assessment of the former Naval Training Center (Paldiski) decommissioning | |
| 1.5 Coordination and approval of the concept of final decommissioning of the former Naval Training Center (Paldiski) | |
| 1.6 Taking decision on the final decommissioning of the former Naval Training Center (Paldiski), including a decision on fundim | g. |
| 1.7 Development of program including plan of its implementation. Development of design documentation. Licensing. | |
| 2. Works on the site of the former Naval Training Center (Paldiski) | |
| 2.1 Infrastructure refurbishment (equipment for waste management, handling, environmental protection and safety) | |
| 2.2 Preparation for waste management (preliminary): relocation, handling, packing and placement of waste (solid) | |
| 2.3 Dismantling of building structures of the RCs and its premises, waste handling and disposal of low-level waste, | |
| 2.4 Dismantling of the equipment of the primary circuit and pressurized water reactor, waste handling and disposal | |
| 2.5 Intermediate processing and exemption of waste that remains after previous (earlier) activities, (and) dismantled infrastruction | cture |
| 2.6 RC building decontamination | |
| 2.7 Decontamination and complete cleaning of the site | |
| 2.8 Complete disassembly of the building and facilities on the site | |
| 2.9 Area remediation | |
| Final stage | |
| 3.1 Procedure of exemption of the former Naval Training Center (Paldiski) from regulation for the radiation hazardous facilities | 1 |
| 3.2 Site transfer to national economy (restricted use) | |
| 3.3 End-pont "Brown Field" | |
| PRELIMINARY STUDIES FOR THE DECOMMISSIONING OF THE REACTOR COMPARTMENTS OF THE FORMER PALDISKI MILITARY NUCLEAR SITE AND FOR THE ESTABLISHMENT OF A RADIOACTIVE WASTE REPOSITORY | .1 |



| 346B decommissioning various options | | | | | |
|---|-----------|---------------------------|-------------|--------------------------|--|
| | Stand | 346 A | Stand 346 B | | |
| Waste denomination | Mass, kg | Volume, m ³ | Mass, kg | Volume m ³ | |
| Concept A Dismantling of RC with large-sized fragm | entation | | | | |
| Long-lived ILW, LLW from dismantling of RC primary circuit equipment | 115,000 | 220 | 210,000 | 384 | |
| Waste from RC dismantling (removed from under control and non-radioactive) | 740,000 | 370 | 740,000 | 370 | |
| Radioactive waste from the concrete cutting with RW inside the compartments (categories of ILW compartments with IRS, LLW, VLLW - for the rest of the concrete compartments) | 656000 | 73 | 906000 | 55 | |
| Waste from sarcophagus dismantling (non-radioactive) | 650,000 | 650 | 610,000 | 610 | |
| Total RW | 180,000 | ~293 | 300,000 | 439 | |
| Total of non-radioactive waste | 1,390,000 | 1020 | 1,350,000 | 980 | |
| Concept B Dismantling of RC with small-size fragm | entation | | | | |
| Long-lived ILW, LLW from dismantling of RC primary circuit equipment | 115,000 | 197 | 210,000 | 288 | |
| Waste from RC dismantling (removed from under control and non-radioactive) | 740,000 | 370 | 740,000 | 370 | |
| Radioactive waste separated from the concrete inside the compartments (category of ILW compartments with IRS, LLW, VLLW - for the rest of the concrete compartments) | 15,000 | 17 | 10,000 | 17 | |
| Concrete (non-radioactive) | 50,000 | 50 | 80,000 | 80 | |
| Waste from sarcophagus dismantling (non-radioactive) | 650,000 | 650 | 610,000 | 610 | |
| Total RW | 130,000 | 214 | 220,000 | 305 | |
| Total of non-radioactive waste | 1,440,000 | 1070 | 1,430,000 | 1060 | |
| Concepts C and D RC disposal as a whole | | | | | |
| Radioactive waste of category ILW, LLW in RC volume | 920,000 | ~700 | 1,040,000 | 900 | |
| Waste from sarcophagus dismantling (non-radioactive) | 650,000 | 650 | 610,000 | 610 | |
| Total RW | 920,000 | 700 | 1,040,000 | 900 | |
| Total of non-radioactive waste | 650,000 | 650 | 610,000 | 610 | |

Substage 3.4. Preliminary indication of waste volumes of stands 346A and 346B decommissioning various options

For transporting and disposal of the RPVs of stands 346A and 346B it is recommend one type of container (2,8x4,8), although the size and weight of the RPV of 346B is much more than 346A (50 t and 30 t). According to the IAEA regulations for the transportation the Type A package is required for this RW. Developing an appropriate container, designed for all required types of impacts is very expensive task, and is estimated at about 500 000 euro and the cost of manufacture of such a container could be about 80 000 euros. Therefore, it is desirable to develop as little as possible of new containers and if possible to use existing ones. In order to save funds it seems to be useful to develop one type of container for every suitable case. Concept B requires container of type A package for the disposal of both RPV and for fragments of two shielding tanks.

Development of the container: development of the construction, conducting computational studies for conformity with the required parameters, prototyping, conduct confirmation testing for compliance with the requirements, manufacture of sample, cask certification.

A.L.A.R.A. 🛄 🚬

PRELIMINARY STUDIES FOR THE DECOMMISSIONING OF THE REACTOR COMPARTMENTS OF THE FORMER PALDISKI MILITARY NUCLEAR SITE AND FOR THE ESTABLISHMENT OF A RADIOACTIVE WASTE REPOSITORY



| Initial event | Initial events consequences |
|--|---|
| External effects of natu | iral and man-made disasters |
| Earthquake (4.7 by the Richter scale) | Structures designed for earthquake of 7 points on MSK-64 scale (approximately 4,8 on the Richter scale) |
| Hurricanes, tornadoes | May result in the partial destruction of the roof and falling of the fragments of the bridging. |
| Rains (abnormal) | Does not result in flooding of the building (location on flat terrain at ~ 25 m above sea level) |
| Typhoons and tsunamis | MTB building is located outside the impact area of the hydrological phenomena. |
| Snow load 1.8 kN/m | The bridging is designed for such loads |
| Fhunder / lightning | All electrical equipment is grounded and earthed, lightning protection is provided for |
| Air shock wave as a result of explosion | The pressure of the air shock wave in case of explosion of a tank is approximately 2.5 kPa and it does not lead to the destruction of MTB structures. |
| Fall of an aircraft / flying object | No considerable damage from light aircraft (up to 5 t). Heavy aircraft (20 t or more) will destroy the sarcophagus structure, can cause depressurization of RC shell, but not break unit primary circuit, a possibility of fire break-out will not lead to dispersion of radioactivity in the atmosphere. |
| Internal impacts cause | ed by accidents inside the building |
| Fire inside MTB building | Heating of contaminated equipment during a fire not lead to dispersion of radioactivity in the atmosphere. |
| Fall of the overhead crane | Deformation of the of the pressure shell, possibility of mechanical equipment damage of the primary circui (crumple, breaks of the shell, etc.). The release of radionuclides is insignificant. |
| Fall of the reactor vessel (RV) | Release of radionuclides is insignificant, the radiation background slightly increased, and the event does not prevent further work (after 50 years of storage - dosage rate from reactor vessel be within 0.2 mSv/h. |
| Fall of the SRW container (destruction of the container) | When falling from various heights, there are various consequences. The container can become depressurized, but reactor vessel will remain inside the container. No release of the radioactivity from reactor vessel. Radiation environment around the container will remain within the emergency standards. |

Subtask 3.5. Decommissioning safety assessment, taking into account the waste quantities to be generated

| Analysis of the Risks in Emergency Situations and Assessment of Their Consequences | Description of | Radio | Effe | ctive D | ive Dose of Internal Radiation, Sv, at a distance, km | | | | |
|---|--|--------|--------------|--------------|---|--------------------------|-----------------------------------|--------------|--------------|
| | Emergency nuclide Situation | 1 | 1.3 | 1.8 | 3 | 4.5 | 6 | 8 | |
| Assessment of dose exposure in a | | Co-60 | 1.88 E-12 | 2.37 E-12 | 2.19 E-12 | 1.78 E-12 | 1.32 E-12 | 1.08 E-12 | 7.57 E-13 |
| situation when a source (most active) is opened and becomes completely unenclosed 1) non-destroyed $P_A = \frac{Q \cdot K_Y}{R^2}$ | Burning of Containers With Solid Radioactive Waste | Eu-152 | | 2.48 E-12 | 2.29 E-12 | 1.86 E-12 | 1.37 E-12 | 1.13 E-12 | 7.91 E-13 |
| | | Eu-154 | | 9.34 E-13 | 8.64 E-13 | 7.05 E-13 | 5.19 E-13 | 4.27 E-13 | 2.99 E-13 |
| | | Cs-137 | | 5.51 E-12 | 5.12 E-12 | 4.18 E-12 | 3.08 E-12 | 2.52 E-12 | 1.77 E-12 |
| | | Total | | 1.13 E-11 | 1.05 E-11 | 0.5 E-11 | 6.29 E-12 | 5.17 E-12 | 3.61 E-12 |
| 2) scattered as along the line at a distance of approximately 50 cm gamma source | | | | | | | Activity according to certificate | | |
| $P_{A} = \frac{2n \cdot K_{\gamma}}{h} \cdot \operatorname{arctg} \frac{l}{h}$ Cobalt- GIK-5-2 | | | | | | | 3.16x10 ¹² Bq | | |
| In case of an emergency situation the personnel must leave the emergency situation area and mayor to a cafe place (5 min) GIK-2-18 | | | | | | 5.11x10 ¹¹ Bq | | | |
| the emergency situation area and move to a safe place (5 min). One-time individual exposure will not exceed 0.1 mSv | | | | cob | egory alt-60 g | | 1.02x10 ¹⁰ Bq | | |
| Source GIK-2-14 PRELIMINARY STUDIES FOR THE DECOMMISSIONING OF THE REACTOR COMPARTMENTS OF THE FORMER PALDISKI MILITARY NUCLEAR SITE AND FOR THE ESTABLISHMENT OF A RADIOACTIVE WASTE REPOSITORY | | | | | | | | | |

